



PLAN VIEW

GENERAL NOTES:

1. CEMENT CONCRETE SHALL BE CLASS 4,000 CONCRETE PER SECTION 6-02 OF THE WSDOT STANDARD SPECIFICATIONS.
2. CONTRACTION PLANE JOINTS FOR CEMENT CONCRETE SHALL BE PLACED AT 2 TIMES SIDEWALK WIDTH OR 10' MAXIMUM AND SHALL MATCH SCORES IN SIDEWALK WHERE APPLICABLE.
3. 3/8" EXPANSION MATERIAL SHALL BE PLACED AT ANY STRUCTURE. MAXIMUM 100' SPACING. EXPANSION JOINT SHALL EXTEND THE FULL CONCRETE DEPTH.
4. SUBGRADE AND CTC UNDER ALL CURBING SHALL BE COMPAKTED TO 95%.
5. EXCEPT FOR JOINTS AND BROOM FINISHING, NO OTHER MARKINGS ARE PERMITTED ON THE FINISHED SURFACE.
6. MAINTAIN CONSISTENT CROSS SLOPE TO STRUCTURE.
7. IF STORM STRUCTURE REQUIRES A HOODED GRATE SEE STANDARD PLAN S-115 FOR ADDITIONAL INFORMATION.
8. COORDINATE WITH ENGINEER FOR OTHER STRUCTURE TYPES THAT MAY REQUIRE A LONGER TAPER.



ELEVATION VIEW



PAVEMENT EDGE DETAIL

PAGE 1 OF 1



APPROVED BY:

ROBERT B. BLEGEN, P.E.
PUBLIC WORKS DIRECTOR

CURB AND
GUTTER PAN

STANDARD PLAN NO.
R-101

PUBLICATION DATE: 09/2025

REVISION NO.: 00